

Prefabricated Low Pressure Residential Meter Set

UPSCO's proprietary line of Prefabricated Meter Sets are manufactured to meet your specifications. We offer standard designs and customized units tailored to meet your needs with a variety of options. We feature 100% pressure testing, custom packaging, custom stocking programs, and continued service and support from product development through final installation.

- Complete assembled Meter sets from a Low pressure 250 class meter to welded 4" welded rotary meter. Can be supplied as a completed turnkey assembly, all units pressure tested, painted and packaged to your specification. We can help you design meter sets or offer suggestions for you current design. We make meter sets the way you want them. We only use the highest quality components that easy installation and have been proven to give years of good service in all types of environments. **If you want it done right call UPSCO.**
- Assembly with Meter regulator bracketing if desired Meter sets are available in sizes 3/4" to 1-1/2" for in lines services of 175 psi.
- Threads conform to ANSI B2.1
- Center stabilizing hole in the flat stock for easy one screw attachments of stabilizing brackets.
- Locking valves, available in insulated or non-insulated, are 100% leak tested from the manufacturer.

